

BOQ OF MUHAMMAD YOUSUF CHACHAR SCHOOL GH

Construction of 2 classrooms of size 16'x24', 2 class rooms of size 16'x20', of size, 16'x10', washroom of size 16'x20' together with 425'ft long & 8 ft l boundary wall and corridors.

| S.NO: | DETAIL OF WORK | QTY | UNIT | RATE |
|--|---|--------|------|------|
| <u>Civil Work for classroms, corridor, washroom & Boundary wall</u> | | | | |
| 1 | Excavation | 3,564 | Cft | |
| 2 | Concrete | 1,834 | Cft | |
| 3 | Brick massonary work in 1:4 cement sand mortar below DPC | 1,473 | Cft | |
| 5 | Reinforcement | 3,872 | kg | |
| 6 | DPC with steel of 3soot on foundation brick massonary | 910 | Cft | |
| 7 | Brick massonary work above DPC | 6,969 | Cft | |
| 8 | Lental work on window & door alongwith shades on windows | 220 | Cft | |
| 9 | Roof with TR 900gms/P.Ft, guarder 3Kg/P.Ft, tiles, plastic sheets & mud | 2,104 | Sft | |
| 10 | Plaster work | 19,820 | Sft | |
| 11 | CC Flooring | 2,543 | Cft | |
| 12 | R.C.C. stair | 230 | Sft | |
| 13 | Windows of 3x4 made of MS sheet 16 guage | 17 | Nos | |
| 14 | Door of 3.5x6.5 made of MS sheet | 6 | Nos | |
| 15 | White Wash of Inside & outside of the entire building & wash rooms | 19,820 | Sft | |
| 16 | Oil Paint of door and windows | 1,900 | Sft | |
| 17 | Iron Gate 10x7 with RCC pillars | 1 | Job | |
| Total | | | | |
| <u>Electric Work</u> | | | | |
| 1 | Supply & Installation of solar system 3.2 KVA with Invertor (Inverex) | 1 | Job | |
| 2 | Solar Plate 330W | 7 | Nos | |

| | | | | |
|-----------------------------|--|----|-----|--|
| 3 | Solar Motor | 2 | Nos | |
| 4 | Battery 200 AMP | 2 | Nos | |
| 5 | Complete Electric fitting | 1 | Job | |
| 6 | AC DC Fan | 20 | Nos | |
| 7 | Bulb | 50 | Nos | |
| Total | | | | |
| <u>Pulmbing work</u> | | | | |
| 1 | Complete pulmbing work. (03 Wash room) W.C. with Flash Tab & Wash Basin) | 1 | Job | |
| Total | | | | |
| Grand Total | | | | |

IOTKI

**Staff room
high**

AMOUNT

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

-

